BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016 **Indent No.20433**

SCHEDULE-B

NAME OF WORK: Maintenance of footpath in ward no.13, Shetty halli sub division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **UMESHA H C**		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	7
1	Removing and resetting of Footpath slab. complete as per specfication & as per direction of Engineer-in-charge	Sqm	1782	110.0	Rupees One Hundred Ten Only	196020.00
2	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed complete as per specfication & as per direction of Engineer-in-charge	Cum	1228	140.0	Rupees One Hundred Forty Only	171920.00
3	Removing B.S.Slab of drain and stacking etc., complete complete as per specfication & as per direction of Engineer-in-charge	Sqm	356.4	60.0	Rupees Sixty Only	21384.00
4	Refixing Stone slabs of drains and pointing in CM 1:3 etc . complete as per specfication & as per direction of Engineer-in-charge	Sqm	356.4	70.0	Rupees Seventy Only	24948.00
5	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & complete as per specfication & as per direction of Engineer-in-charge	Sqm	273	1500.0	Rupees One Thousand Five Hundred Only	409500.00
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading complete as per specfication & as per direction of Engineer-in-charge	Cum	1228.8	70.0	Rupees Seventy Only	86016.00
					Total	909788.00
					Percentage	-8.07%

Signature of the Contractor

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Executive Engineer